

**SURVEY &
REMONUMENTATION**

APR 27 1995

LIBER

1 PG 1237

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
94 DEC 30 AM 9 18

For corners in

Kalamazoo

(County)

Brady Township

1. Public Land Survey

Located In:

Corner Code #

T 4 S R 10 W

F-12

T

R

T

R

T

R

T

R

2. Property Controlling
in Section

S

S

S

S

T

T

T

T

R

R

R

R

3. Miscellaneous
Property in Sec.

S

S

T

T

R

R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on June 7, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		14		15		16		17		18		
7													
8	19		20		21		22		23		24		
9													
10	25		26		27		28		29		30		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Position Not Established by Original Surveyors

1919: Kalamazoo County Road Commission; Center of Section noted at Center Line Station 185+80. No description of monument or witnesses other than in line with fence to North.

Date Unknown: Kalamazoo County Surveyor Records;

Iron Fence Post North 29.55'
Northeast Corner Culvert 114.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 1/2" x 18" pinch pipe at surface. Found a large (14" x 12" x 8") stone 1.38' West and 0.65' North of iron.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-15-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-12 Center of Section 33, T. 4 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994. Found stone at witnesses from "A" above. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Lowered stone and placed a 20" Harrison monument and monument box over stone.

Center Line "YZ" Avenue		South	0.5'
Notch in Railroad Rail	Fence Corner	North 04° East	29.80'
PK Nail in Southeast Side	Power Pole	North 42° East	59.15'
PK Nail in Northeast Side	23" Walnut	South 40° East	47.05'
PK Nail in Northwest Side	20" Walnut	South 70° West	73.30'

Signed by

Robert E. Snell

Date

12/28/94

Surveyor's Michigan License No.

9734