

SURVEY &
REMONUMENTATION

FEB 18 1994

LIBER

1 PG 1028

STATE OF MICHIGAN
COUNTY OF KALAMAZOO

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

RECEIVED FOR RECORD

Filing Requirement of Act 74, Mich. P.A. 1970,

93 NOV 18 PM 3 46

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Brady Township		
1. Public Land Survey	T 4 S R 10 W	G-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

James P. Young
CLERK-REGISTER

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7							●						
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826,
 Accessories: W Oak 10 S21W 12½. W Oak 6 S62E 13.
 Survey by Ed Strong, County Surveyor, 1875, Found Stone by Nutting, no accessories.
 Survey by H C Fleming, 1915, Iron Rod, Accessories: 4" Cherry South 35.3', 3"
 Cherry S W 39.5'. Survey by Perry McPherson, 1972, Found Iron, Accessories: 32"
 Locust S3W 34.05', 28" Oak N77W 130.09', Fence Post N3½W 31.27'.
 Survey by Allen McMachen, 1973, Found Iron in Monument Box, Accessories: 24" Oak
 N75W 130.17', 30" Locust S2W 34.32', Fen Cor North 29.95'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Original Corner and Accessories not recovered.
 Stone by Nutting found by Ed Strong, 1875, not recovered.
 Found Irons by Fleming, McPherson & McMachen.
 Found ½" Iron in Monument Box - Found ½" Iron 1.70' West and 0.86' North of Iron
 in Monument Box - Found Brick with Stone around, 36" below surface, 1.33' West
 and 1.78' South of Iron in Monument Box.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 G-7, Section Corner 15, 16, 21 & 22, T4S-R10W, Ratified by Kalamazoo County
 Remonumentation Program Peer Group on September 16, 1993. Found ½" Iron in Monument
 Box. Found ½" Iron 1.70 West & 0.86' North of Iron in Monument Box. Found Brick
 with Stone around 1.33' West and 1.78' South of Iron in Monument Box and is
 accepted as the best available evidence of the position of the original Corner.
 Removed Monument Box and both ½" Irons. Placed 20" Harrison Monument above Brick
 with Stone around and placed Monument Box over Corner.

- Set P.K. Nail in 26" Oak N5W 103.60'
- Set P.K. Nail in 42" Willow South 30.22'
- Set P.K. Nail in P.P. S50E 66.56'
- Set P.K. Nail in 10" Cherry S50W 81.97'

Signed by *John G. Kester* Date 11-17-93
 Surveyor's Michigan License No. 16046
 Kalamazoo County Road Commission