

SURVEY &
REMONUMENTATION

FEB 18 1994

LIBER

1 PG 1029

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'93 NOV 18 PM 3 46

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Brady Township		
1. Public Land Survey	T <u>4</u> S R <u>10</u> W	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James T. George
CLERK-REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John G. Kester, in a field survey on August 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Accessories: Br Oak 18 S19W 88, R Oak 16 S70 $\frac{1}{2}$ E 1.18.
Survey by H C Fleming, 1914, Iron Rod, Accessories: Oak N E 31.2', Double Elm N6W 19.7'
Survey by Kalamazoo County Road Commission, 1970, Found Iron in Monument Box, Accessories: 4" Iron Fence Corner N10W 34.47', S E Cor Hdwl S15W 14.05'. 24" Oak S75W 68.22'. Survey by Perry McPherson, 1972, Found $\frac{1}{2}$ " Iron, Accessories: Triple Maple N21 $\frac{1}{2}$ E 91.17', 3" Maple N29W 38.58', Center Steel Culvert End S23W 33.00'.
Survey by Allen McMachen, 1973, Found Iron in Monument Box, Accessories: 24" Maple N75E 119.25', 14" Hickory S75W 149.75', 22" Oak South 101.72'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner & Accessories not recovered.
Iron found by Road Commission in 1970 believed to be same Iron by H C Fleming in 1914, accessories gone. Road Commission removed Iron & Monument Box in 1972, for muck excavation and sand backfill, and replaced with $\frac{1}{2}$ " Iron in Monument Box, no accessories. Survey by McPherson, 1972, Found $\frac{1}{2}$ " Iron, accessories gone. Survey by McMachen, 1973, Found Iron in Monument Box, accessories good.
Found $\frac{1}{2}$ " Iron in Monument Box and nothing else as all other corner evidence was removed during 1972 road construction. Found Accessories: 31" Maple N75E 119.25', 21" Hickory S75W 149.75', 29" Oak South 101.72'.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7, S $\frac{1}{4}$ Corner Section 15, T4S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found $\frac{1}{2}$ " Iron in Monument Box and is accepted as the best available evidence of the position of the Original Corner. Removed Iron & Monument Box. Placed 30" Harrison Monument in place of removed Iron and placed Monument Box over Corner.

- Set P.K. Nail in 12" Maple South 58.15'
- Set P.K. Nail in 20" Poplar S45E 60.98'
- Set P.K. Nail in 15" Hickory N45E 48.15'
- Set P.K. Nail in 8" Maple N20W 36.77'

Signed by *John G. Kester* Date 11-17-93

Surveyor's Michigan License No. 16046

Kalamazoo County Road Commission