

1995

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 AUG 25 PM 3 51

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo Located In: _____ Corner Code # _____
(County)

Brady Township

1. Public Land Survey T 4 S R 10 W H-12
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

Jeanette Jones
CLERK-REGISTER

LIBER 1 ■ 1325

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Garth N. Baden, in a field survey on June 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
This corner not established by original government surveyors.
1919: Kalamazoo County Road Commission field notes.
Stone-Center Section 34
Δ = 0° 15' L
Hickory 22" South 45° West 49.0'
Hickory 30" North 45° West 51.5'
Walnut 15' North 45° East 48.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1990: Wilkins & Wheaton Engineering Company; Placed PK Nail.
Hickory 30" South 45° West 50.15'
Railroad Rail Fence Post North 45° West 41.18' West Side
Chainlink Fence Corner 46.15'
1994: Found PK Nail at surface. Found 12" x 6" x 4" stone 6" below surface--Stone had drill hole in top.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5-18-95 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-12 Center of Section 34, T. 4 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on May 18, 1995 and is accepted as the best of available evidence of the position of the Corner. This position not established by original government surveyors. Found a PK Nail at surface and a 12" x 6" x 4" stone 6" below surface and 0.38' East and 0.11' South of PK Nail. Stone was called for in 1919 Kalamazoo County Road Commission field notes. Lowered stone and placed a 20" Harrison monument and monument box over stone.
Notch in Top Railroad Rail Fence Post North 46° West 41.20'
Top of 2" Chain Link Fence Corner North 50° East 46.75'
PK Nail in East Side 41" Oak South 36° East 50.02'
PK Nail in East Side 15" Hickory North 14° West 75.09'

Signed by *Garth N. Baden* Date Aug 22, 1995