

SURVEY & REMONUMENTATION

FEB 18 1994

LIBER 1 PG 1030

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'93 NOV 18 PM 3 46

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Brady Township		
1. Public Land Survey	T <u>4</u> S. R <u>10</u> W	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

James F. Young
CLERK-REGISTER

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826,
Accessories: W Oak 12 S57E 48½, W Oak 13 N63W 7.
Survey by Ed Strong, County Surveyor, 1872, Found Stake Hole from one living witness, Set Stone - Leaded and Marked, Accessories: Black Oak 10 S33E 32 Lks.
Survey by H C Fleming, 1914, Buggy Axle, Accessories: Elm N W 65.0'. Oak N E 51.3'.
Survey by Perry McPherson, 1972, Found ½" Iron, Accessories: 8" Maple S28½W 77.85', P.P. N4½W 42.65', 8" Oak S61E 104.75'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Original Corner & Accessories not recovered.
Stone & Accessories by Ed Strong, 1872, not recovered.
Found T Iron over ½" Iron in Monument Box, Accessories: none recovered.
Found Buggy Axle with Stone around and one large Stone on top 46" below surface as called for in 1914 Survey by Fleming, accessories gone. Buggy Axle is 2.11' South and 2.29' West of T Iron over ½" Iron in Monument Box.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-7, Section Corner 14, 15, 22 & 23, T4S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found T Iron over ½" Iron in Monument Box. Found Buggy Axle with Stone around and one large Stone on top as called for in 1914 Survey by Fleming and is accepted as a careful and faithful perpetuation of the position of the original Corner. Removed T Iron, ½" Iron and Monument Box. Placed 30" Harrison Monument above large Stone over Buggy Axle with Stone around and placed Monument Box over Corner.

- Set P.K. Nail in P.P. South 52.64'
- Set P.K. Nail in 13" Hickory S22W 76.98'
- Set P.K. Nail in 8" Oak N30E 88.25'
- Set P.K. Nail in 20" Oak S40E 96.21'

Signed by *John G. Kester* Date 11-17-93

Surveyor's Michigan License No. 16046
Kalamazoo County Road Commission