

**SURVEY & REMONUMENTATION**

NOV 25 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in Brady Twp.

Kalamazoo  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey

T	4S	R	10W	I-09
T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

2. Property Controlling in Section  
3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
98 OCT 22 AM 11 37  
Clerk - Register

LIBER 2PAGE 344

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on May 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP 5-21-1998**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors; set post, corner to Sections 22, 23, 26 and 27.  
White Oak 16" N. 11° E. 30 lks.  
White Oak 12" S. 35° E. 25 lks.
- 1873: S. Hodgman, County Surveyor; stone set by Emery (Surveyor) correct by roots of both trees.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1938: Wilkins & Wheaton Engr. Co.; witness book, stone by Emery, B.O. 20" N. 63 3/4° W. 53 lks., W.Cherry 20" S. 23 1/2° W. 94 3/4 lks., W.O. 16" S. 53° E. 37 lks, W.O. 42" N. 58° E. 41 lks. - found stone below 2' pl. iron above.  
30" Maple N. 05° E. 28.9 ft.  
24" Maple N. 60° E. 69.4 ft.
- 1975: Wayne Mostrom, RLS #14100; L.C.R.C. L-1, P-559; 1/2" iron bar found (over stone), 32" Maple N. 05° E. 28.9', 26" Maple N. 60° E. 69.4', center line of East & West Road on Section line and in fence line projected North.
- 1998: Found capped iron in monument box (#16935) over trapazoid stone 2 ft. deep over several smaller stones with brick.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-09: Southeast corner, Section 22, T. 4 S., R. 10 W., ratified on May 21, 1998 by the Kalamazoo County Remonumentation Program Peer Group and is accepted as a careful and faithful perpetuation of the position of the original corner. Found iron over stones and brick set by Emery and verified by S. Hodgman, County Surveyor in 1873 survey placed 20" Harrison monument in monument box over stones and brick.  
PK Nail in East Side 36" Maple N. 42° E. 37.72'  
PK Nail in West Side Old Telephone Pole S. 44° E. 53.30'  
PK Nail in East Side Power Pole N. 52° W. 48.48'  
PK Nail in West Side 14" Elm N. 08° W. 41.98'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 10-22-98