

SURVEY & REMONUMENTATION

FEB 18 1994

LIBER

1 PG 1031

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'93 NOV 18 PM 3 46

COMMISSION

For corners in

| | | |
|------------------------------------|----------------------------|---------------|
| <u>Kalamazoo</u> (County) | Located In: | Corner Code # |
| Brady Township | | |
| 1. Public Land Survey | T <u>4</u> S R <u>10</u> W | <u>J-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Jamaal P. Young
CLERK-REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, John G. Kester, in a field survey on August 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Accessories: Elm 10 S4E 21, B Ash 12 N49W 11. Survey by Ed Strong, County Surveyor, 1872, Bisected 3-4 for point - correct by Roots of one witness. Set Stone, Leaded & Marked, Accessories: Elm 4 N27 $\frac{1}{2}$ E 25 Lks, Elm 12 S40 $\frac{1}{2}$ E 66 $\frac{1}{2}$ Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner and Accessories not recovered. Found $\frac{1}{2}$ " Iron alongside $\frac{1}{2}$ " Iron in Well Point in Monument Box. Found Stone with chiseled X on top with small Stone around and large Stone on top 5.50' East and 1.11' North of Irons in Well Point in Monument Box. No accessories found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7, S $\frac{1}{4}$ Corner Section 14, T4S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found $\frac{1}{2}$ " Iron alongside $\frac{1}{2}$ " Iron in Well Point in Monument Box. Found Stone with Chiseled X on top with small Stone around and large Stone on top and is accepted as a careful and faithful perpetuation of the position of the original Corner. Removed Monument Box but left $\frac{1}{2}$ " Irons in Well Point in place. Reset large Stone on S E side of Stone with chiseled X and placed 20" Harrison Monument above Stone with chiseled X. Placed Monument Box over Corner.

- Set P.K. Nail in 28" Hickory N10W 27.65'
- Set P.K. Nail in 24" Walnut N35W 44.90'
- Set P.K. Nail in 16" Box Elder S55E 29.72'
- Set P.K. Nail in 6" Twin Maple South 39.60'

Signed by *John G. Kester* Date 11-17-93
Surveyor's Michigan License No. 16046
Kalamazoo County Road Commission

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93**