

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Brady Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>10W</u>	<u>J-09</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

98 OCT 22 AM 11 37

CLERK - REGISTER

LIBER 2 PAGE 345

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
1826: United States Government Surveyors; set 1/4 post.
Beech N. 77° W. 17½ lks.
Beech N. 62½° E. 45 lks.

1872: S. Hodgman, County Surveyor; stone, set by Emery; correct by both stumps.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1975: Wayne Mostrom, RLS#14100; L.C.R.C. L-1, P-559, R.R. spike found, R.R. rail N. 30° W. 36.1', power pole N. 40° E. 39.95', R.R. rail S. 45° W. 44.37'
1998: Found railroad spike 3" below surface, then found old PK Nail + 3.5' north of railroad spike. Then found large (1.35'x.70'x.70') stone in middle of five stones. High point of stone was 3.5' ± north of railroad spike.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5-21-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-09: South 1/4 post, Section 23, T. 4 S., R. 10 W., ratified on May 21, 1998 by the Kalamazoo County Remonumentation Program Peer Group and is accepted as a careful and faithful perpetuation of the position of the original corner. Found large stone in cluster of stones, set by Emery and verified by S. Hodgman in 1872 Survey placed 8" of 10" Harrison monument in monument box over stone.

PK Nail in East Side	Power Pole	North	50.71'
PK Nail in West Side	Power Pole	N. 62° E.	32.92'
PK Nail in West Side	Power Pole	S. 35° W.	59.90'
Southeast corner	Railroad Rail Fence Post	N. 12° W.	31.59'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 10-22-98