

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '95 AUG 31 AM 11 25

COMMISSION ON LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KALAMAZOO Located In: _____ Corner Code # _____
 (County)

BRADY TWP.

1. Public Land Survey T 4 R 10 _____ K6
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Jessie Young
 CLERK-REGISTER
1 1344
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GARY D. HAHN, in a field survey on APRIL 29, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U.S. Deputy Surveyor Robert Clark, Jr., 1826.
 Accessories: Beech 16 S57°W 21 lks.
 Beech 15 S73°E 73 lks.

1872 S. Hodgman - Found Stake. Correct by 2" stump beds.
 Noted without marking.
 Accessories: Sugar 3" N23 1/2 E 104 1/2 lks.
 Blk. Walnut 3" N24 1/2 W 104 lks.

KCRC notes call for stone - no accessories - no date.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner with accessories not recovered.
 Fnd. 1/2" dia. rebar 24" long in mon. box buried 6" below asphalt road.
 Removed rebar and fnd. 9"x13"x18" stone with point up 20" deep. The west flat side of the stone and its point were butting against the east side of the rebar.
 Stone and rebar were virtually in same location. Held rebar for witness ties.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
R.E.F.
 6-15-96



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K6, E1/4 Corner Section 14, T4S, R10W, Ratified by Kalamazoo County Remonumentation Peer Group on June 15, 1995. Found 1/2" rebar 24" long in mon. box and along side a 9"x13"x18" pointed stone. 1/2" rebar is accepted as the best available evidence of the position of the original corner.
 Removed rebar and stone and set 30" Harrison monument in mon. box.
 Accessories: Fnd. 1/2" rebar west 33.03'
 Set P.K. Nail in 18" Oak S70°E 62.59'
 Set P.K. Nail in 11" Twin Oak N75°E 80.05'
 Set P.K. Nail in 27" Oak N77°W 30.29'

Signed by *Gary D. Hahn*
 Surveyor's Michigan License No. 38116

Date AUGUST 18, 1995