

SURVEY &
REMONUMENTATION

FEB 18 1994

COMMISSION

LIBER

1 PG 1032

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'93 NOV 18 PM 3 46

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Brady Township		
1. Public Land Survey	T 4 S R 10 W	K-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Jama B. Young
CLERK-REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John G. Kester, in a field survey on August 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		14		15		16		17		18		
7													
8	19		20		21		22		23		24		
9													
10	25		26		27		28		29		30		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826,
Accessories: Beech 8 N33E 12, Beech 8 N41W 31.
Survey by Ed Strong, County Surveyor, 1872, Found Stake Hole from Stump of one witness. Set Stone with Leaded Center & side Stone S 50 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner & Accessories not recovered.
Found 1/2" Iron in Monument Box - Found Cut Stone 6" square on top by 18" long, with Leaded 1/2" drill hole, and Stone around (as called for in 1872 Survey by Ed Strong) 1.75' North and 0.54' East of 1/2" Iron in Monument Box.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7, Section Corner 13, 14, 23 & 24, T4S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found 1/2" Iron in Monument Box. Found Cut Stone 6" square on top and 18" long, with Leaded 1/2" drill hole, with Stone around and is accepted as a careful and faithful perpetuation of the position of the original Corner. Removed 1/2" Iron and Monument Box. Placed 20" Harrison Monument above Leaded Stone and placed Monument Box over Corner.

- Set P.K. Nail in 25" Oak N30E 63.99'
- Set P.K. Nail in P.P. N30W 66.63'
- Set P.K. Nail in 11" Maple S45E 48.04'
- Center Bell Manhole S25W 50.95'

Signed by *John G. Kester* Date 11-17-93

Surveyor's Michigan License No. 16046
Kalamazoo County Road Commission