

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'95 AUG 31 AM 11 34

For corners in
KALAMAZOO
(County)

Located In:

Corner Code #

BRADY TWP.

1. Public Land Survey	T	4	R	10	LI
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous	S		T		R
Property in Section	S		T		R

[Signature]
CLERK-REGISTER

LIBER 1 1339

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GARY D. HAHN, in a field survey on MAY 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not set during G.L.O. survey.

1976 LCRC Liber 1, Page 648 Donald R. Gilchrist
.22 barrel in mon. box
Triple Maple S45°E 31.03'
4" Oak N15°W 32.47'
8" Maple N25°E 52.53'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found .22 cal. rifle barrel in mon. box 0.7' below asphalt road. Dug 3' into natural dark clay under barrel. Found no evidence of any other marker or monument.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-15-95
R.E.G.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L1, North quarter post Section I, T4S, R10W, Ratified by Kalamazoo County Remonumentation Peer Group on June 15, 1995. This position not established by original government surveyors. This monument (.22 cal. rifle barrel) is accepted as the best available evidence of the position of the corner. Removed rifle barrel and replaced with a 20" Harrison Monument in mon. box.
Set P.K. nail in 9" Twin Oak N10°W 33.36'
Set P.K. nail in 8" Triple Oak N50°E 45.98'
Set P.K. nail in 12" Triple Oak S40°E 29.61'
Set P.K. nail in 12" Oak S50°W 47.11'
Fnd. 1/2" rebar West 10.91'

NOTE: This corner was ratified as a closing corner.

Signed by *[Signature]*
Surveyor's Michigan License No. 38116

Date 8-29-95