

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'95 AUG 31 AM 11 35

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KALAMAZOO (County) Located In: Corner Code #

**BRADY TWP.**

1. Public Land Survey	T	<u>4</u>	R	<u>10</u>	<u>L5</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		

*James Young*  
CLERK-REGISTER

LIBER 1 1343

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GARY D. HAHN, in a field survey on MAY 1, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter post established by U.S. Deputy Surveyor Robert Clark, Jr., 1826  
Accessories: Beech 12 S48°W 20 lks. Beech 14 N1°E 17 lks.  
1872 S. Hodgman D.L.S. "Stone set by nutting (with drill hole) side stones N&S 50 lks. each"  
1905 E. Strong Co. Sur. "B. Walnut 2 S10°W 41½ lks. Found 3 stones of Nutting centerstone drilled 6" deep. Set 8" below road"  
Date ? KCRC notes: Stone Accessories: iron fence post N. 32.5' Hickory 26" N60°E 88.6'  
Walnut 14" S. 89.0'  
1977 McMachen LCRC L.1 P.715 Stone with "X" 15" Hick. NE. 48.35' 20" Wal. S. 88.94'  
18" Hick. SW. 65.42' Centerline "V" Ave. 1' North.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike in Mon. Box. Found large flat stone with "X" directly under spike 13" below road surface. Stone was 1.9' x 1.3' x 3.5'. Removed stone. Found no stone with drill hole. Probed down 4' - 5'. Found no further evidence. Road does not appear to have been filled.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
6-15-95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L5, South 1/4 Corner Section 12, T.4S., R.10W., Ratified by Kalamazoo County Remonumentation Peer Group on June 15, 1995. Found large flat stone with "X" directly under found R.R. spike in Mon. Box. Spike and stone location is accepted as a careful and faithful perpetuation of the position of the original corner. Removed spike and stone and replaced with a 30" Harrison monument in box.  
Found nail w/tab in 16" Black Walnut S10°W 27.22'  
Set P.K. nail in 5" Maple N59°E 48.29'  
Set P.K. nail in 5" Ash S42°E 49.46'  
Set P.K. nail in 21" Maple North 49.44'

Signed by *Gary D. Hahn*

Date August 18, 1995

Surveyor's Michigan License No. 38116