

SURVEY &  
REMONUMENTATION

FEB 18 1994

LIBER

1 PG 1033

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

93 NOV 18 PM 3 46

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Brady Township		
1. Public Land Survey	T <u>4</u> S R <u>10</u> W	<u>L-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Jamie Young*  
CLERK-REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John G. Kester, in a field survey on August 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826,  
Accessories: Sugar 8 N40E 9, W Ash 18 N81W 14.  
Survey by Ed Strong, County Surveyor, 1872, Bisected 3-4 Set Stone with Lead center and marked large Stone ➡➡ S54W 35 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner and accessories not recovered.  
Found 1/2" Iron in Monument Box above Cone shaped Stone with Drill Hole believed to be Stone called for by Ed Strong Survey in 1872. Accessories not recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7, S 1/4 Corner Section 13, T4S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found 1/2" Iron in Monument Box above Cone shaped Stone with drill hole (Removed 1/2" Iron and Monument Box. Placed 20" Harrison Monument above Cone shaped Stone with drill hole and placed Monument Box over Corner) and is accepted as a careful and faithful perpetuation of the position of the original Corner.

- Set 6" Spike in 10" Box Elder S15W 48.96'
- Set 6" Spike in 9" Box Elder N15W 34.25'
- Set 1/2" Rebar S50E 42.44'
- Center of South End 40" CMP S10W 31.43'

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
9-16-93

Signed by *John G. Kester* Date 11-17-93

Surveyor's Michigan License No. 16046

Kalamazoo County Road Commission