



LC-000044
Page: 1 of 1
10/28/1999 03:11P
Bk-2 Pg-497

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|--------------------------|--------------|
| <u>Kalamazoo</u> (County) | Located In: | Corner Code# |
| Brady Twp. | | |
| 1. Public Land Survey | T <u>4S</u> R <u>10W</u> | <u>M4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

SURVEY & REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

I, Gary D. Hahn, in a field survey on August 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Corner established by U.S. Deputy Surveyor Robert Clark, Jr.: "Set 1/4 sec. post in Indian path east W. Oak 18 S 15° W 69 L. W. Oak 10 N 45° W 41 L."

1905 - E. Strong Co. Sur.: "Lost. Set drilled stone Cherry 6 East .50 Elm 18 N 89° W .57"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found a 1/2" diameter 18" long rebar in a 2" diameter 3" long pipe in asphalt road. Measured 105.49 feet to a 1/4" rod at Wakeshma corner A-4. Found a 10" x 13" x 18" stone with point lying on its side pointing north. Straightened stone and found a drill hole on the point. Stone was in gravelly sand about 2.5 feet below road surface just under old road bed. The position of the straightened stone was 0.61 feet North and 0.51 feet West of the surface marker. Removed the stone to excavated a 5' x 5' x 5' deep hole. No other evidence found. Reset the stone at a distance of 105.49' North of a 1" diameter pipe found below the road surface at the Wakeshma corner and at the same easting as the 1/2" rebar surface marker. Stone is at a depth of 19" below road surface. It was the decision of the Kalamazoo County Remonumentation Peer Group to reestablish this corner at the bisection of Brady Township corners M-3 and M-5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M4, East Quarter Post Section 12, Town 4 South, Range 10 West. Ratified by the Kalamazoo County Remonumentation Peer Group on September 23, 1999. The location of the bisection of the line made up by Brady Township corners M-3 & M-5 is accepted as a careful and faithful reestablished of the position of the corner. Set a 20" Harrison Monument in a monument box at said bisection.

Witness Ties: Found Pk nail in 18" Ash N 54° E 38.09'
Found PK nail in 12" Ash S 58° E 35.82'
Found nail w/tab 10" Ash S 40° W 40.42'
Found nail w/tab in fence post S 80° W 32.21'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-23-1999



Signed by [Signature]
Surveyor's Michigan License No. 38116

Date 10/18/99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,

JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983 REVISED OCT., 1995