



LC-000046
 Page: 1 of 1
 10/28/1999 03:11P
 Bk-2 Pg-499

WIGHTMAN WARD LANDCOR-Kalamazoo
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo Located In: _____ Corner Code# _____
 (County)
 Brady Twp.
 1. Public Land Survey T 4S R 10W M5
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**SURVEY &
 REMONUMENTATION**

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary D. Hahn, in a field survey on August 5, 1999
 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner
 points mentioned in lines 1 and 2 above were in conformance with regulations and rules
 therefore as required in the current manual of survey instructions of the United States
 Department of the Interior, Bureau of Land Management or by a decree of a Court of Law
 and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance
 with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law;
 established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded
 on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Corner established by U.S. Deputy Surveyor Robert Clark, Jr.: "Set post cor. secs. 12 & 13
 W. Oak 17 S 28 ° W 64 L. Wh.Oak 18 _____ 94 L."

1872 - Sam Hodgman: "Stone w/hole set by Nutting correct by roots of one witness".

1905 - E. Strong: "S. stone of Culvert drilled N 65 ° E 15" = a witness tie! Found drilled stone by Nutting 8" below road".

K.C.R.C. Witness Ties:

- (W) Fd. drilled stone 1/31/52
- (W) Elm 30" S 40 ° W 54.73'
- (W) Tele. Pole NE 39.14'
- (W) End culvert NE 29.27'
- (W) End culvert SE 56.98'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 9-23-1999

1977 - L.C.R.C. L. 1, P.715, A. McMachen: "Iron in 2" pipe U.P. N.E. 40.30 feet 7" Butternut NW. 58.95 feet S. edge stop sign SW.
 51.85 feet Centerline/centerline 36th Street & V Avenue West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found a 1/4" diameter 6" long rod in a 2" diameter 3" long pipe. Removed. Found a 5/8" diameter
 20" long pipe driven over a 1/4" diameter rod about 2 feet below road surface. Rod was 1.07 feet North and 0.10 feet East of the surface rod.
 Removed. Found a 13" x 15" flat surface stone with a 3/4" drill hole in the center at a depth of 3.8 feet below the road surface. Drilled hole was 1.17
 feet North and 0.10 feet East of the surface rod.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M5, Northeast Corner Section 13, Town 4 South, Range 10 West. Ratified by the Kalamazoo County Remonumentation Peer Group on September 23,
 1999. The position of the drilled hole on the found stone is accepted as a careful and faithful perpetuation of the position of the original corner. Set a
 20" Harrison Monument in a monument box directly over drill hole.

Witness Ties: Set 1/2" rebar flush w/curb N 24 ° E 41.16'
 Set 1/2" rebar flush w/curb N 28 ° W 53.28'
 K.C.R.C. BM Mon. (in curb) S 38 ° W 49.21'
 Set 1/2" rebar flush w/curb S 78 ° E 41.09'



Signed by [Signature]
 Surveyor's Michigan License No. 38116

Date 10/18/99