



LC-000048
Page: 1 of 1
10/28/1999 09:11P
Bk-2 Pg-501

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code#
Brady Twp.		
1. Public Land Survey	T <u>4S</u> R <u>10W</u>	<u>M6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY &
REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Gary D. Hahn, in a field survey on August 6, 19 99
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner
points mentioned in lines 1 and 2 above were in conformance with regulations and rules
therefore as required in the current manual of survey instructions of the United States
Department of the Interior, Bureau of Land Management or by a decree of a Court of Law
and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance
with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law;
established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Comer established by U.S. Deputy Surveyor Robert Clark, Jr.: "Set 1/4 sec. post W. Oak 12 S 11 1/2 ° W 89 Lk. W. Oak 8 N 46 1/2 ° W 77 L."

1872 - Sam Hodgman: "Corner lost. Bisected 2 - 3 and set square stone with lead center and side stones NW + SW 70 5/8 Lks. each".

1977 - L.C.R.C. L. 1, P.715, A. McMachen: "Iron in mon. box. U.P.S. S.W. 43.71 feet 14" Wal. S. SE. 95.5 feet U.P. N. NW. 75.86 feet Box South 90.2 feet".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found a 1/2" diameter 12" long rod in a monument box. Removed. Found a 5/8" diameter 16" long rod at a depth of 27" below the road. Rod was 0.25 feet North and 0.09 feet West of the surface rod. Removed. Found a 4" x 7" x 12" ± rectangular stone w/definite corners centered under the 5/8" diameter rod at a depth of 34" below the road surface. No lead center found.

C. Description of monument for comer and accessories established to perpetuate locating the position of the corner:

M6, East Quarter Post Section 13, Town 4 South, Range 10 West. Ratified by the Kalamazoo County Remonumentation Peer Group on September 23, 1999. The position of the found stone is accepted as the best available evidence of the position of the original comer. Set a 20" Harrison Monument in a monument box directly over found stone.

Witness Ties: Set 1/2" rebar at edge of asphalt N 16 ° E 34.61'
Set 1/2" rebar at edge of asphalt S 24 ° E 32.90'
Set PK nail in P.P. S 34 ° W 43.76'
Found PK nail in P.P. N 18 ° W 74.68'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-23-1999



Signed by [Signature]
Surveyor's Michigan License No. 38116

Date 10/18/99