

FEB 08 1999

LIBER

2 PAGE 404

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo

(County)

Brady Twp.

1. Public Land Survey

T 4S R 10W

M7

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

Located In:

Corner Code#

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Gary D. Hahn, in a field survey on October 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Established by U.S. Deputy Surveyor Robert Clark, Jr.:
Beech 6" S 26 W 32 Lks. Beech 7" N 78 W 26 Lks.

1872 - F. Hodgman - V 1, P. 254, 255 "Found stake hole correct by stump of 1 witness. Set large pointed stone & others around it and marked."
W. Ash 28" S 69 W 137 1/2 Lks.
Elm 24" N 24 E 58 Lks.

KCRC Witness Ties:
NE Cor. Bldg. NW 76.27'
SE Cor. Bldg. NW 74.89'
SW Cor. Sec. 18 Wak. Twp. South 74.60'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 - Original monument and accessories not recovered. Found 1/2" rebar in mon. box. Removed. Found 5/8" rod 1 1/2' deep 0.35' south & 0.27' west of 1/2" rebar. Removed. Found five 8" - 10" round stones around one pointed stone 4.5' below road surface. Point of stone is 0.31' south & 0.32' west of 1/2" rebar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7, Southeast Corner Section 13, Town 4 South, Range 10 West, ratified by Kalamazoo County Remonumentation Peer Group on November 19, 1998. Position of the stone is accepted as a carefull and faithful perpetuation of the position of the original corner. Set 30" Harrison Monument in a Monument Box directly over point of stone.

Witness Ties:

Set Mag. Nail in Guard post N 55 W 26.32'
Set Mag. Nail in Guard post S 75 W 48.09'
Most Ely. Cor. "Landmark" corner store N 26 W 76.14'
Harrison monument in mon. box South 74.29' [G.L.O. JOG = 74.58']

Signed by [Signature]
Surveyor's Michigan License No. 38116

Date 12/08/98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983 REVISED OCT., 1995

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 3 05
CLERK - REGISTER

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

11/19/98 [Signature]

