

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 395

For corners in Schoolcraft Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T4S R 11W	A-03
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 9 15
Clerk - Registrar
Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on July 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1826: United States Government Surveyors; entered West boundary 61 lks. North of post for which stands W. Oak 7 in.
 - 1889: F. Hodgman, County Surveyor; "Found stone of former survey in place 61 lks. North of corner stone to Sections 1 & 12. Which stone is S. 60° E. 22 lks. from remains of W. Oak U.S. Bearing Tree. Set post, corner to Sections 6 & 7." Maple (3rd in row) S. 48° W. 142½ lks. Maple 3" (1st in row) S. 15½° W. 141¼ lks.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1940: Wilkins & Wheaton Engr. Co.; found tile 4' below. Place 1" pipe 3 ft. long + ½" iron 1 ft. long.
 - 1998: Found 3/4"x4' pipe in monument box with ½" iron in rod. Found 1" pipe down 3½' bent to South found pieces of brick from 4' to 6' around pipe returned later (12-9-98) and found tile down 6½' below surface. Surface iron was 0.15' North and 0.28' East of tile. Noted centerline "U" Avenue South 31.5'.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8/20/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-03: Southwest corner, Section 6, T. 4 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on August 20, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3/4"x4' pipe and 1"x3' pipe over tile (6½' deep) in monument box. Tile was placed in 1889 Remonumentation survey by F. Hodgman, County Surveyor. Placed 30" Harrison monument in monument box above tile.

PK Nail (4' high) in West Side	8" Maple	N. 20° E.	66.78'
PK Nail (4' high) in South Side	Power Pole	N. 87° E.	73.00'
PK Nail (4' high) in South Side	Power Pole	N. 60° W.	60.80'
PK Nail (4' high) in South Side	Power Pole	N. 50° W.	42.14'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-18-98