

SURVEY & REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

7
2
APR 27 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'94 DEC 14 PM 2 38

For corners in

<u>Kalamazoo</u> <small>(County)</small>	Located In:	Corner Code #
Schoolcraft Township	T <u>4</u> S R <u>11</u> W	<u>A-6</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James J. [Signature]
CLERK - REGISTER

LIBER **1** PG **1204**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1870: F.Hodgman, County Surveyor; West 1/4 Post Section 18. Found the corresponding corner on Section 13, T. 4 S., R. 12 W. from one witness. Planted Tamarack, stake, and stone. Thence North on the Range Line at 58½ Links. Planted stake and stone for 1/4 Section Corner and noted;

Maple 8" North 87½° East 58 Lks
Maple 8" North ½° East 135 Lks

1909: Ed Strong, County Surveyor; Schoolcraft Stone, North 58½ Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 1/2" x 12" iron in monument box, 38.61'± North of Prairie Ronde Corner (not dug up). Found a stone at 1.0' below surface. Stone has a crow's foot notch and a drill mark with broken clay tile around stone. Found old stake remains below stone.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-15-94
R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 West 1/4 Post Section 18, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994. Found old stake, stone, and iron in monument box as called for in 1870 survey by F.Hodgman. This Corner not established by original government surveyors. This monument is accepted as the best available evidence of the position of the Corner. Removed stake remains, lowered stone and placed a 20" Harrison monument and monument box over.

PK Nail in East Side	Power Pole	N 15° E 81.98'
PK Nail in North Side	Power Pole	N 84° E 35.85'
Exist. Nail/Tab in North Side	Power Pole (high line)	N 84° W 55.80'
Bolt in Light Pole (2' above ground)		S 02° W 61.78'
CL "U" Avenue (Lyons Street)		South 32.5'
CL 12th Street		West 3.5'

Signed by *Robert E. Snell* Date 12-14-94

Surveyor's Michigan License No. 9734