

MAY 1 6 1996

COMMISSION

STATE OF MIGHIGAN #OUNTY OF KALAMAZOO RECEIVED FOR RECORD


'98 MAR 13 PM 3 42

LAND CORNER RECORDATION CERTIFICATE

Ec	or corners in	Filing Requireme	A. 1970	
_	Kalamazoo County) Schoolcraft Twp.	Located In:	Corner Code #	James Plane
1.	Public Land Survey	T <u>4 S. R 11 W</u> . T R T R T R	A-07	CLERK-REGISTER
2.	Property Controlling in Section	S T R S T R		LEBER 1 1447
3.	Miscellaneous Property in Section	S T R S T R		Register of Deeds Stamp & File Number
	Lot No, Re Private Claims	corded Plat		A B C D E F G H I J K L

Robert E. Snell, in a field survey on <u>January 30</u> do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the comer points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.



Original United States Government Surveyors; intersected West boundary 117 lks. North of post. Set post at intersection, corner to Sections 18 and 19.

> N. 36° E. Ironwood 6"

W. Ash 30"

S. 40° E.

6 1ks.

1888: F. Hodgman, County Surveyor; found iron, brick, and bearing tree of resurvey all in place, set post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1951: Wilkins & Wheaton Engr. Co.; found iron, tile, brick and stone.

50" Elm S. 580 W. 18.91

1¼" Iron Pipe South 36" Sugar Maple N. 70° E. 36.2' in traveled center line of road

48.95'

1974: Don Gilchrist, R.L.S. #13583; L.C.R.C. L-1, P-613 tile

> S. 30° W. 18" Ash 74.64' s. 40⁰ 36" Maple 111.40' Ε. N. 10⁰ E. Twin 12" Ash 32.581

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 2-15-96

Found 3" round tile – top broken 3" below surface with brick around, East edge of concrete drive S. 70° W. 3.33' iron in traveled center line South 36.2'. 1996:

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Southwest corner Section 18, T. 4 S., R. 11 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on February 15, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile (top broken) as set by F. Hodgman, County Surveyor in 1888 Remonumentation Survey. Placed a remonumentation sleeve over tile.

PK Nail in West Side	12" Maple	S. 42 ⁰ E.	2.651
PK Nail in North Side	7" Ash	N. 72 ⁰ W.	25.84'
PK Nail in East Side	12" Maple	N. 18 ⁰ W.	9.31'
PK Nail in North Side	18" Maple	S. 85 ⁰ W.	44.24

	/ /	1-5		01
Signed by	1/6400	7 2.	1 Zac	

3-12-96