



LC-000086  
Page: 1 of 1  
12/17/1999 02:03P  
Bk-2 Pg-538

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Schoolcraft Twp.

Kalamazoo Located in: Corner Code #  
(County)

1. Public Land Survey T 4 S R 11 W A-08  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SURVEY &  
REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on Nov. 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

This corner not established by original Government Surveyors.

1935: Wilkins & Wheaton Engr. Co.; established corner on bisection of West line of Section 19, T. 4 S., R. 11 W. between tiles at Northwest corner and Southwest corner. Corners established by F. Hodgman, County Surveyor in 1889 Remonumentation survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1999: Found 1/2" x 22" iron in swamp as set in 1935 survey.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-08: West 1/4 post, Section 19, T. 4 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 9, 1999 and is accepted as a careful and faithful establishment of the position of the corner. This corner not Established by original Government Surveyors. Found iron (3/4" x 22") of Wilkins & Wheaton Engr. Co. survey of 1935 on Bisection. Placed 30" Harrison monument in swamp in place of iron.

1/2" iron (found)	in North right-of-way GTW Railroad	S. 0°-17' W.	215.01'
PK Nail in East Side	14" Wild Cherry	S. 4°-17' W.	168.16'
PK Nail in South Side	12" Willow (center trunk)	N. 89°-45' E.	307.04'
Center	Harrison Monument (M-08 Prairie Ronde)	South	38.61'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 12/16/99

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
12/19/99