

SURVEY & REMONUMENTATION

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

2 PAGE 383

For corners in Schoolcraft Twp.

Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T 4 S	R 11 W	A-13
This corner is common to Schoolcraft (A-13) and Prairie Ronde (M-13)	T	R	
2. Property Controlling in Section	S	T	R
3. Miscellaneous Property in Sec.	S	T	R

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 NOV 23 PM 2 58
J. J. [Signature]
CLERK - REGISTER
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Apr. 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 4-16-1998

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; intersected range line 452 lks. South of temporary six mile post. Set post at intersection, corner to Townships 4 & 5 South, Ranges 11 & 12 West.

Br. Oak 12" S. 72¹/₄⁰ W. 225.5 lks.
W. Oak 12" N. 86¹/₄⁰ W. 263 lks.

1889: F. Hodgman, County Surveyor; found old corner stone at corner of hedge. Set post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1956: Michigan State Highway Department, U.S. 131 Plans; distance from N 1/4 post of Section 6, T. 5 S., R. 11 W. to NW corner is 2,264.13' with jog of 38.28' East = 2,302.41'

1998: Found 1 ft. Section of 3" round tile laying on its side. Found second section setting upright in good condition just below top and on West side of large stone down about 1 1/2'. Noted SW corner concrete transformer pad N. 10⁰ W. 7.54', SE corner concrete transformer pad N. 30⁰ E. 8.3', "T" fence post Northeast 1.15'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13: Southwest corner Section 31, T. 4 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on April 16, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top along side large stone as set by F. Hodgman in 1889 Remonumentation survey. Placed remonumentation sleeve over tile.

NE Corner	Concrete Fence Post	N. 40 ⁰ W.	0.92'
SE Corner	Concrete Fence Post	S. 80 ⁰ W.	0.66'
NW Corner	Concrete Fence Post	S. 40 ⁰ W.	0.58'
NE Corner	Concrete Fence Post	S. 40 ⁰ E.	0.92'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 11-20-98