

SURVEY & REMONUMENTATION

FEB 26 1998

7-
2. SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Schoolcraft Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T4S R11W	B-03
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

LIBER
CLERK - REGISTER

2 PAGE
97 DEC 29 AM 10 56

281
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

STATE OF MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Aug. 23, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3	7		8		9		10		11		12		
4													
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set 1/4 Section post.
Br. Oak 6" N. 17° E. 52 lks.
Br. Oak 6" N. 59° W. 60 lks.

1889: F. Hodgman, County Surveyor; "Found stone set S. 59° E. 60 lks. from B. Oak bearing tree, standing. Set post. Burr Oak 20" S. 33° E. 76 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1942: Wilkins & Wheaton Engr. Co.; Found tile in ring and cover.

1960: MSHD, H.G. McManus #6935; Boat spike, 14" Oak N. 80° E. 148.79', 12" Ash S. 75° E. 140.04', T. Pole N. 75° W. 106.09'

1997: Found 1" pipe 3.5' long in monument box. Dug at least 1' in all directions of 1" pipe and found no other evidence. Pipe believed to be set by MSHD in construction of U.S. Route 131. Note: Box is in south bound lanes of U.S. Route 131.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12/18/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-03" South 1/4 post, Section 6, T. 4 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 18, 1997 and is accepted as the best available evidence of the position of the original corner. Found 1-inch pipe believed to have been set by M.S.H.D. in 1950's construction of U.S. Route 131. Removed pipe and placed 20" Harrison Monument in monument box.

Arrow in Northwest Base	Steel Guy Pole	S. 65°-42' E.	111.11'
Arrow in North Base	Steel Guy Pole	S. 53°-43' W.	94.16'
Capped Iron (Red)	Near Clearvision Fence	N. 68°-34' W.	135.77'
Notch "x" in Northeast Base	Guy Pole	N. 46°-03' W.	75.70'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-23-97