



LC-000089
Page: 1 of 1
12/17/1999 02:03P
Bk-2 Pg-542

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Schoolcraft Twp.

Form with fields for Kalamazoo (County), Located in: T 4 S R 11 W, Corner Code # B-05, and numbered sections 1-5 for survey details.

SURVEY & REMONUMENTATION
FEB 08 2000
SECTION

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on Nov. 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A circle is drawn at the intersection of row 5 and column B.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: United States Government Surveyors, R. Clark; West between Sections 7 and 18, 40 chains. Set 1/4 Section post in prairie and raised mound: 77.90 chains entered West boundary at post (mound in prairie).
1870: F. Hodgman, County Surveyor; "Original 1/4 post lost. Divided Section line proportionately and planted stake and stone, from which Maple 3" N. 87° W. 46 lks., Cherry 6" S. 89° E. 64 lks. Another stake about 10 lks. West not properly established by (M. M.) Stimson is incorrect."
1889: F. Hodgman, County Surveyor; "Found stone with stake under and bearing trees of resurvey standing."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1939: Wilkins & Wheaton Engr. Co.; placed iron in pavement from witness. In fence lines East and West, Maple 26" N. 87° W. 29.0', 12" Elm S. 87° E. 26.5', 24" Maple N. 45° W. 43.9'.
1960: Michigan State Highway Department, N.G. McManus, RLS #6935; found 3/4" iron rod. 25" Oak N. 05° E. 33.17' 27° Oak S. 65° W. 55.73' 13" Sassafras N. 60° W. 71.94'
1964: Michigan State Highway Department, Projects 39-6, 39-7 Route U.S. 131 (Map 3); 1/4 corner is 0.90' E. of center line of South bound lanes.
1969: Wilkins & Wheaton Engr. Co.; field notes call for lead plug - not in line.
1999: Witnesses gone - new pavement over concrete highway. Re-established by running South line of Section and divided proportionately. Placed "mag nail" at corner and 1/2" x 18" irons at intersection of right-of-way's, 130' East and 70' West. Government measure 77.90 chains measure 5,201.95' - B-05 - S. 1/4 to E. 1/4 C-05 = 2,671.09. Directed by Peer Group to move corner 1.72' South to match lead plug as noted in 1964 and 1969 above.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-05: South 1/4 post, Section 7, T. 4 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 9, 1999, and is accepted as a careful and faithful re-establishment of the position of the original corner. Established South line by proportionately bisecting to Government measure (see "A" above). Government 1/2 mile = 40.0 chains (2,640.00'), Mile = 77.90 chains (5,141.00'). Placed South 1/4 post at 2,671.09 feet from Southeast corner and measured mile at 5,201.95'. Set "mag" nail in center line of South bound lanes of U.S. Route 131 in South line of Section 7, then moved Southerly 1.72' as directed by Peer Group and set "mag" nail. Placed 30" Harrison monuments on relocated Section line at intersection of both right-of-way lines, 130.00' East and 70.00 West.

Straight line between Southwest corner and Southeast corner assumed = East and West.

Harrison Monument - West Right-of-way
PK Nail in S. Side, 14" Ash, S. 83°-19'-35" W., 36.47'
PK Nail in E. Side, Power Pole, S. 04°-52'-46" E., 6.35'
Mag Nail in E. Face, Sign Post (Church), S. 07°-43'-55" W., 46.26'
Top of Conc. Post, Pipe Line Marker, S. 0°-35'-43" W., 93.88'

Harrison Monument - East Right-of-way
SW. cor. (Wood Siding), Hse #12991, N. 52°-45'-10" E., 39.59'
Top of Conc. Post, R-O-W Marker, S. 56°-50'-38" W., 2.13'
1/2" Iron (Found), N. 35°-33'-38" W., 2.81'
PK Nail in W. Side, Power Pole, S. 19°-34'-16" W., 4.02'
Top of E. end, 15" Conc. Culvert, N. 87°-41'-38" W., 19.40'
Top of Conc. Post, Pipe Line Marker, S. 00°-59'-11" W., 29.51'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12/16/99

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 12/16/99