

# SURVEY & REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
94 DEC 6 PM 3 55

1.  
2.  
APR 27 1995

## LAND CORNER RECORDATION CERTIFICATE

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo  
(County)

Located In:

Corner Code =#

Schoolcraft Township

1. Public Land Survey		T	4	S	R	11	W	C-2
		T		R				
		T		R				
		T		R				
		T		R				
2. Property Controlling in Section	S	T		R				
	S	T		R				
3. Miscellaneous Property in Sec.	S	T		R				
	S	T		R				

*James J. Jones*  
CLERK-REGISTER

LIBER 1 PG 1181

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on April 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1826: U.S. Government Survey; Set 1/4 Section Post.

W. Oak 14" North 24° West 31½ Lks  
W. Oak 11" South 31° East 32 Lks

1871: F. Hodgeman, County Surveyor; At the West 1/4 Section Corner of Section 5, found stone planted in the woods. Both witnesses still standing.

1889: F. Hodgeman, County Surveyor; Found stone with brick under and U.S. Bearing Trees all in place. Set Post.

1983: Al McMachen; Found Tile. LCRC Liber 1, Page 858 18" Maple S 70° E 45.10' 12" Fence

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.  
14" Oak S 60° W 38.78' Post S.1.0'

1994: Found 3" round tile at surface with brick around.

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**  
4/22/94  
*R.E. Snell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2 East 1/4 Post Section 5, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on April 20, 1994. Found 3" round tile as called for in 1889 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed a remonumentation sleeve over tile.

CL Top	G.T.E. Telephone Pedestal	South	9.60'	SW Cor Mobile Home
Nail/Tab in West Side	30" Hickory	South 05° West	38.26'	N 87° E 10.03'
PK Nail in East Side	24: Hickory	North 10° West	70.28'	
CL Top	G.T.E. Telephone Pedestal	West	46.18'	

Signed by *Robert E. Snell* Date 12-05-94

Surveyor's Michigan License No. 9734