

FEB 18 1994

LIBER

1 PG 1005

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Schoolcraft Township		
1. Public Land Survey	T 4 S R 11 W	C-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

CLERK - REGISTER

James J. [Signature]

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
93 OCT 25 AM 9 38

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John G. Kester, in a field survey on July 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U.S. Government Deputy Surveyor Robert Clark, 1826, Post in Mound in Prairie no accessories. Survey by E. Strong, 1870, Found Stake and Stone - Planted Stone 16" long with smaller stone around, Accessories: Maple 3" N56 $\frac{1}{2}$ E 106 $\frac{1}{2}$, Maple 3" N17 $\frac{1}{2}$ E 159. Resurvey by F. Hodgeman, 1889, Found Stone set for Corner S56 $\frac{1}{2}$ W 106 $\frac{1}{4}$ Lks from Maple Bearing Tree. Set Post (Solid Clay Tile), Accessories: Maple 6" S59E 86 Lks, Maple Bearing Tree N56 $\frac{1}{2}$ E 106 $\frac{1}{4}$ Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner Post and Accessories not recovered. Found Monument Box over 3/8" iron rod over 3/4" pipe with brick & stone around over Solid Clay Tile with "X" on top as called for in 1889 Resurvey by F. Hodgeman, Accessories gone.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8-19-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7, Section Corner 17,18,19 & 20, T4S-R11W, Ratified by Kalamazoo County Remonumentation Program Peer Group on August 19, 1993. Found Solid Clay Tile with "X" on top as per 1889 Resurvey and is accepted as a careful and faithful perpetuation of the position of the original corner. Removed existing Monument Box, iron & pipe. Placed 20" Harrison Monument above Tile and Placed Monument Box over Corner.

- Set P.K. Nail in P.P. N 45 W 48.12'
- Set P.K. Nail in 20" Walnut S 50 W 56.63'
- Set P.K. Nail in P.P. N 22 E 99.66'
- T/Bolt Hydrant S 25 E 72.80'

Signed by John G. Kester Date 10-20-93
Surveyor's Michigan License No. 16046
Kalamazoo County Road Commission

