

FEB 18 1994

LIBER 1 PG 1004

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
93 OCT 25 AM 9 38
CLERK - REGISTER

For corners in

Table with columns: Kalamazoo (County), Schoolcraft Township, Located in:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column C and row 7.

I, John G. Kester, in a field survey on July 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U.S. Government Deputy Surveyor Robert Clark, 1826, Post in Mound in Prairie no accessories. Resurvey by F. Hodgeman, 1889, Found old Stake in center of road & in line with East side of fences North & South. Set Post (Solid Clay Tile with "X" on top), Accessories: Maple 10" S58E 115 1/2 Lks, Maple 12" S14E 62 Lks - 6th in row from West.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner Post not recovered. Found Monument Box over 3/4" iron above Solid Clay Tile with "X" on top as called for in 1889 resurvey by F. Hodgeman. Accessories for 3/4" iron, S.E. Corner R.R. Rail on end North 32.68'. All other accessories gone.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8-19-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7, S 1/4 Corner Section 17, T4S - R11W, Ratified by Kalamazoo County Remonumentation Program Peer Group on August 19, 1993. Found Solid Clay Tile with "X" on top as per 1889 resurvey and is accepted as a careful and faithful perpetuation of the position of the original Corner. Removed existing Monument Box and 3/4" iron. Placed 20" Harrison Monument above Tile and placed Monument Box over Corner.

- Set P.K.Nail in 17" Spruce N 3 E 72.83'
Set P.K. Nail in 18" Walnut S 50 W 67.65'
Set P.K. Nail in 26" Maple S 15 E 50.33'
Set P.K. Nail in 32" Maple N 50 E 68.96'
S.E. Corner R.R. Rail on end North 32.68' (Existing)

Signed by John G. Kester

Date 10-20-93

Surveyor's Michigan License No. 16046

Kalamazoo County Road Commission

