

**SURVEY & REMONUMENTATION**

MAY 16 1996

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

1 1460

For corners in Kalamazoo  
(County)  
Schoolcraft Twp.

Located In:

Corner Code #

- |                                      |                         |       |
|--------------------------------------|-------------------------|-------|
| 1. Public Land Survey                | T 4 S. R 11 W.          | D-11  |
|                                      | T _____ R _____         | _____ |
|                                      | T _____ R _____         | _____ |
|                                      | T _____ R _____         | _____ |
| 2. Property Controlling in Section   | S _____ T _____ R _____ | _____ |
|                                      | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
|                                      | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
1996 MAR 25 PM 3 30  
*Donna J. [Signature]*  
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on February 9, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1826: United States Government Surveyors; set 1/4 Section post in prairie and raised mound.  
1889: F. Hodgman, County Surveyor; found stone of former survey at intersection of fences. Set post.  
Locust 5" about N. 20° E. 5 lks.  
Locust 5" West 90½ lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1986: Acro Engineering; found tile - no witnesses.  
1996: Found tile just below surface.

**RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP**  
3-21-96  
*[Signature]*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-11: South 1/4 post, Section 29, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on March 21, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top as placed by F. Hodgman, County Surveyor in a Remonumentation survey in 1888 just below surface. Placed a Remonumentation sleeve over tile.

PK Nail in West side	North & South fence	East	0.85'
PK Nail in West side	14" W. Cherry	North	8.30'
PK Nail in West side	12" W. Cherry	S. 05° W.	7.50'
PK Nail in East side	Double 24" Oak	South	60.25'

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 3-25-96