SURVIVA
REMONUMENT

_____, Recorded Plat ___

3. Miscellaneous

5. Private Claims ___

COUNTY OF KALAMAZOO

RECEIVED FOR RECORD '95 APR 26 AM 11 09 AUG 2 2 1995

MONTER CONTRA	LAND CORNER REGORDATION CERTIFICATE
COMMISSION	Filing Requirement of Act 74 Mich. P.A. 1970


	CONTRACTOR OF		
iling Requi	rement of Act 74, Mich	. P.A. 1970)	Turner of the state of the stat
Un:	Corner Code -++		The state of the s

i di comera m			11 miles
Kalamazoo (County)	Located In:	Corner Code ##	CLERK - REGISTER
Schoolcraft Township		{	,
Public Land Survey	T <u>4 S</u> R <u>11 W</u>	D-13	
	T R		•
•	T R		4 61000
	T R		LIBER 1 1 1298
2. Property Controlling	S T R		
in Section	S T R		

Register of Deeds Stamp & File Number Property in Sec.

1. Robert E. Snell , in a field survey on _ December 8 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.



U.S. Government Survey; Set 1/4 Section Post.

North W. Oak 13" 68 1/2° East 240 Lks 14 1/2° W. Oak 8" South 189 Lks West

F. Hodgman, County Surveyor; Set Post (3" round tile) in marsh South 68½° West, 240 Lks 1889: from stump of U.S. Bearing Tree, recently cut.

6" Red Oak North East 92 Lks 6" 54 1/4° Wh. Oak South East 88 1/2 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Wilkins & Wheaton Engineering Company; Found 3" round tile in swamp 11' South of old downed fence.

> RATIFIED BY KALAMAZOO COUNTY **REMONUMENTATION** PEER GROUP

10

12

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- South 1/4 Post Section 32, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on December 15, 1994. Found 3" round tile/cross as called for in 1889 remonumentation survey by F. Hodgman and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed remonumentation sleeve over tile.

PK Nail in East Side PK Nail in South Side PK Nail in North Side PK Nail in Northeast Side	10" Elm 12" Cherry 12" Elm 8" Elm	North 38° East North 67° East South 80° East South 15° East	55.78' 21.12'
Toe of Slope (edge of swamp)	0 2.111		25.1 +

Intl Date 4-26-95 Surveyor's Michigan License No. __