

SURVEY & REMONUMENTATION

2 AUG 06 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **Kalamazoo** **COMMISSION**

(County) Located In: **Schoolcraft Twp.**

Corner Code #

- | | | | |
|--------------------------------------|--------|---------|------|
| 1. Public Land Survey | T 4 S. | R 11 W. | E-01 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Section | S | T | R |
| | S | T | R |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD

96 MAY 23 PM 1 48

CLERK - REGISTER

J. J. [Signature]

LIBER 2 PAGE 013
 Register of Deeds Stamp & File Number

I, **Robert E. Snell**, in a field survey on **April 3**, 19 **96**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; enter North boundary 80 lks. East of post. Set post at intersection of corners 4 & 5.

Tam 8" S. 63° E. 359 lks.
 Y. Oak S. 81° E. 329 lks.

1889: F. Hodgman, County Surveyor; found stake in marsh, 80 lks. East of corner of Sections 32 & 33. Set post.

W. Oak 20" N. 54½° W. 234 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found tile 1' long 3" round laying on its side above second section of tile in good position. Placed top section over good tile measured 52.34' from tile to U.S. Government corner post, as found. Government and Hodgman measured 52.80'.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 4-18-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-01: Northeast corner Section 4, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on April 18, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile as described in "B" above, tile was set by F. Hodgman in 1889 remonumentation survey. Placed remonumentation sleeve over tile.

Center of 20" Harrison Mon. West 52.34'
 PK Nail in West Side 6" W. Cherry N. 02° E. 22.20'
 PK Nail in North Side 5" W. Cherry N. 58° W. 24.45'
 PK Nail in North Side 16" Tamarack S. 78° E. 49.15'

Signed by *Robert E. Snell*
 Surveyor's Michigan License No. **9734**

Date **5-23-96**