

**SURVEY & REMONUMENTATION**

1  
2  
AUG 22 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'95 FEB 9 PM 3 58

For corners in SCHOOLCRAFT TWP.

KALAMAZOO  
(County)

Located In:

Corner Code #

- |                                      |   |   |   |   |    |   |     |
|--------------------------------------|---|---|---|---|----|---|-----|
| 1. Public Land Survey                | T | 4 | S | R | 11 | W | E-3 |
|                                      | T |   | R |   |    |   |     |
|                                      | T |   | R |   |    |   |     |
|                                      | T |   | R |   |    |   |     |
| 2. Property Controlling in Section   | S |   | T |   | R  |   |     |
|                                      | S |   | T |   | R  |   |     |
| 3. Miscellaneous Property in Section | S |   | T |   | R  |   |     |
|                                      | S |   | T |   | R  |   |     |

*James J. Jones*

CLERK-REGISTER

LIBER 1 PG 1271

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Allen H. McMachen field survey on December 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1826 - U.S. Government Survey; set post to Sections 4,5,8 & 9  
Hickory 12" N. 47° W. 211ks.  
Br. Oak 14" S. 58½° E. 1031ks.
- 1889 - F. Hodgeman, C.S., Post gone, both bearing trees standing, set post from them
- 1908 - E. Strong. C.S., Shows using Sec. cor. to Sections 4,5,8 & 9 but does not describe.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found Clay Tile 1.8' below surface.


**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**

1/19/95  
*R.E.S.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found Clay Tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison monument over existing Tile and placed monument box over. Accessories:

- "PK" Nail & Tab in S.E. side Utility Pole N. 50° E. 43.70'
- Nail & Tab in E. side 10" Oak S. 10° E. 37.53'
- Nail & Tab in E. side 18" Oak S. 10° W. 64.70'
- Nail & Tab in N.W. side 6" Twin Pine S. 45° W. 42.90'



Signed by

*Allen H. McMachen*  
16935

Date

2/9/95

Surveyor's Michigan License No.