

AUG 22 1995

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

FEB 9 PM 3 58

For corners in SCHOOLCRAFT TWP.
KALAMAZOO (County) Located In:

Corner Code #

James J. ...
CLERK-REGISTER

LIBER 1 PG 1272

Register of Deeds Stamp & File Number

1. Public Land Survey	T <u>4</u> S <u>R11</u> W	<u>E-4</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Allen H. McMachen a field survey on December 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826 - U.S. Government Survey; Set $\frac{1}{4}$ Section Post
W. Oak 6" N. 82 W. 34 $\frac{1}{2}$ lks.
Hick. 9" N. 69 $\frac{1}{2}$ E. 18 lks.

1889 - F. Hodgeman, C.S., Found stone and both bearing trees of U.S. survey in place. Set Post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile 0.3' below surface in line with fence to West.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
1/19/95
R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed standard sleeve over existing Tile.
Accessories:

- Iron rod with cap NORTH 5.00'
- Nail & Tab in N. side 4" Beech N. 80 E. 4.37'
- Nail & Tab in N. side 6" Oak S. 25 W. 2.66'
- Railroad rail fence post WEST 2.60'
- Nail & Tab in S. side 5" Triple Cherry WEST 14.54'



Signed by *Allen H. McMachen*
Surveyor's Michigan License No. 16935

Date 2/9/95