

**SURVEY & REMONUMENTATION**

AUG 06 1996

7  
2  
**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Kalamazoo  
(County)  
Schoolcraft Twp.

Located In:

Corner Code #

- |                                      |                              |             |
|--------------------------------------|------------------------------|-------------|
| 1. Public Land Survey                | T <u>4</u> S. R <u>11</u> W. | <u>E-08</u> |
|                                      | T _____ R _____              | _____       |
|                                      | T _____ R _____              | _____       |
|                                      | T _____ R _____              | _____       |
| 2. Property Controlling in Section   | S _____ T _____ R _____      | _____       |
|                                      | S _____ T _____ R _____      | _____       |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____      | _____       |
|                                      | S _____ T _____ R _____      | _____       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
96 MAY 23 PM 1 48  
*James R. Young*  
CLERK - REGISTER  
LIBER 2PAGE 015  
Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on April 5, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1826: United States Government Surveyors; set 1/4 post common to Sections 20 and 21 in prairie in a raised mound.  
1889: F. Hodgman, County Surveyor; found old corner stake in tree line between corners and 2 lks. South of center. Set post.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1987: Wilkins & Wheaton Engr. Co.; found tile using back hoe.  
1996: Found tile 12" deep in monument box, 2.5'+ East of center line of road.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
5-16-1996 *R.E.S.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-08: 1/4 post common to Section 20 and 21, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on May 16, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with cross in top as set by F. Hodgman, County Surveyor in a remonumentation survey in 1889. Set remonumentation sleeve over tile.

- |                                     |           |        |
|-------------------------------------|-----------|--------|
| PK Nail on East Side of Power Pole  | N. 24° E. | 74.21' |
| PK Nail on South Side of 32" Walnut | N. 64° E. | 30.03' |
| PK Nail on North Side of 36" Maple  | S. 68° E. | 24.84' |
| PK Nail in North Side of 38" Walnut | N. 82° W. | 35.67' |

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 5-23-96