

SURVEY &  
REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'94 DEC 14 PM 2 39

For corners in

Kalamazoo

(County)

Schoolcraft Township

Located In:

Corner Code #

1. Public Land Survey

T 4 S R 11 W

F-10

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*James J. Jones*

CLERK-REGISTER

LIBER 1 PG 1207

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on June 28, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
Not Set by Government Surveyors.

1879: F. Hodgman, County Surveyor; at Intersection of 1/4 Lines, set stake and stone.

Maple 2" South 72° West 129 1/2 Lks

1927: Kalamazoo County Road Commission; Found stone 6' South Centerline.

Maple 18" South 75° West 87.5'

Maple 24" North 65° West 84.5'

Maple 14' South 70° East 83.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found monument box in Centerline of Road and stone with "X" on top, 4.5' South of monument box. The stone was 7" x 9" x 18". Found stump of 1927 witness.

Maple 18" South 75° West 87.5'

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
9-15-94  
*R. E. Snell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-10 Center of Section 28, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994. Found stone as called for by F. Hodgman in a survey in 1879. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the Corner. Lowered stone and placed a 20" Harrison monument and monument box over.

PK Nail in East Side	18" Walnut	South 03° West 23.51'
PK Nail in South Side	15" Walnut	South 62° East 46.23'
PK Nail in North Side	42" Maple	South 68° East 81.17'
North Edge of Railroad Rail (meas. 2' above ground)		North 02° East 36.95'
CL "XY" Avenue (Mon.Box)		North 4.5'

Signed by

*Robert E. Snell*

Date

12-14-94

Surveyor's Michigan License No.

9734