

OCT 06 1997

COMMISSION

LIBER

2 PAGE 216

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
97 SEP 26 AM 11 10

CLERK - REGISTER

*Annally Johnson*

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Schoolcraft Township  
Kalamazoo  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	4S.	R	11W.	F-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_
- 6. IWM Job No. 30040

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Allen H. McMachen, in a field survey on April 25, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Robert Clark, Jr., D.S., Set quarter section post, Wh. Oak 9' N. 58° W. 128 lks., Wh. Oak 16" N. 35° E. 162 lks.  
 1875 - F. Hodgman, C.S., "Found stake from remains of two witnesses. Planted stone with drill mark and set side stones 50 lks..." (page ripped)  
 1943 - Notes supplied by St. Joseph County Surveyor (Surveyor unknown). Sketch within notes shows meas. from South quarter corner, Section 33 to eighth corner East at 1327.2 feet and jog at South quarter corner of 34.0 feet. Notes read: "175 feet East of Southwest corner, Southeast quarter, Southeast quarter, Sec. 33-4-11 is I.P. [iron pipe] at North side of road. East from I.P. 602 feet = Transit point front of MacDonalds house. 99 feet East of Transit point is well point = 876 feet East of Southwest corner, Southeast quarter, Southeast quarter Sec. 33-4-11."  
 1963 - Wayland D. Ingersoll, R.L.S., Working in Section 4, Park Twp. letter to client states: "...We were unable to find even one of the original government corners in this Section...", Wayland D. Ingersoll placed iron rod at North quarter corner, Section 4 in centerline road and on Northerly projection of fence line to South. Also placed iron pipe at old corner fence post at Northeast corner, Section 4, measured 2648.66 feet between above mentioned corners., Witnesses for North quarter corner: 12" Walnut N. 65° W. 63', 40" Willow N. 13° E. 33.76', 20" Walnut N. 66° E. 81.25'

1975 - Wayne Mstrom, R.L.S., Records L.C.R.C. for North quarter corner, Section 4, Park Twp., "Iron bar found [new]", 10" Double Mulberry N. 41° E. 29.7 feet, 20" Walnut N. 65° W. 62.5 feet, 8" Locust stump South 18.9'  
 1976 - Wilkins & Wheaton, Records Survey in Section 4, Park Twp., L. 402, Pg. 231  
 N¼ cor.  
 ½" iron re-rod  
 "PK" Nail in tree N. 40° E. 29.5'  
 "PK" Nail in 18" Walnut N. 75° W. 62.4'  
 ±1988 - Larkin Winther, R.L.S., Prepares Boundary Survey in Section 33, Schoolcraft Township showing South quarter corner, Section 33 being 35.64 feet West of North quarter corner, Section 4, Park Township and shows distance from South quarter corner, Section 33 to Southeast corner, Section 33 at 2654.72 feet.  
 1996 - Wilkins & Wheaton, Finds Clay tile at Southeast corner, Section 33, Schoolcraft Township and ratifies and records corner, L.C.R.C. L. 1, Pg. 1461.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found North quarter Section 4 as iron in mon. box at the position placed in 1963. Also located I.P. [iron pipe] mentioned in 1943 notes. The Southeast corner, West half, Southeast quarter, Section 33 as placed in ±1988 was also recovered along with the clay tile at Southeast corner, Section 33. The 4 above mentioned markers produce a straight line. Measured 2618.67 feet between North quarter corner, Section 4 and Southeast corner, Section 33. Also measured between the 1943 I.P. [iron pipe] and the eighth post placed in ±1988 at 174.94 feet (1943 meas. 175 feet). S¼ - I.P. "43" meas. = 1502.2, "97" meas. = 1502.05, Excavated at South quarter corner, Section 33 at Government jog of 35.64 feet West of North quarter corner, Section 4 producing a distance of 2654.31 feet between South quarter corner, Section 33 and Southeast quarter Section 33. No corner evidence was found. Placed Harrison Monument at record government jog of 35.64' West of North quarter corner, Section 4, Park Township.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison Monument is accepted as the best available evidence of the position of the corner. Placed Monument box over monument, Accessories:

S.E. corner of Westerly brick & block entry wall N. 65° W. 87.79'  
 S.E. corner of Easterly brick & block entry wall N. 10° E. 37.95'  
 Nail & Tab in Southwesterly side 34" Walnut N. 40° W. 33.81'  
 Nail & Tab in Northwesterly side U. Pole S. 40° W. 46.02'  
 Iron & Mon. box (N¼ cor., Sec. 4, Park Twp.) East 35.64'

Signed by *Allen H. McMachen*  
Surveyor's Michigan License No. 16935

Date 9/25/97



RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
7-16-1997