

SURVEY & REMONUMENTATION

SEP 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Schoolcraft Twp.

Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>4S</u> R <u>11W</u>	<u>6-06</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property In Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
SEP 3 PM 3 26
CLERK - REGISTER

LIBER 2 PAGE 314

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 6-11-1998

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
1826: United States Government Surveyor's; set 1/4 Section post.

Burr Oak 11" N. 87 1/2° E. 172 lks.
Burr Oak 14" N. 21 1/2° W. 200 lks.

1889: F. Hodgman, County Surveyor; "Bisected the mile and at halfway point found stake hole with brick and stones around. Set post."

Burr Oak 20" N. 46 1/2° W. 201 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1972: John Kester, RLS #16046; LCRC L-1, P-213, found 1/2" iron over tile. P.P. S. 85° E. 34.25', U.S.G.S.-B.M. S. 25° W. 82.65', 33' South of "VW" Avenue.

1974: Don Gilchrist, RLS #13583; LCRC L-1, P-525, found tile, reset iron over. P.P. S. 85° E. 34.05' to PK Nail, U.S.G.S.-B.M. S. 25° W. 82.61' corner is 30' South of center line "VW" Avenue.

1998: Found 1/2" x 9" iron, 6" below surface, with 3" round tile with "x" below. Noted center line of "VW" Avenue North 31.2'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-06: West 1/4 post, Section 15, T. 4 S., R. 11 W., ratified June 11, 1998 by the Kalamazoo County Remonumentation Program Peer Group and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 1/2" x 9" iron over 3" round tile with "x" on top 15"± below surface of road. The tile was set by F. Hodgman in a 1889 Remonumentation survey. Placed Remonumentation sleeve over tile with 10" of 16" Harrison monument over in a monument box.

Nail/Tab in South Side	Power Pole	N. 42° E.	69.84'
Nail/Tab in South Side	Power Pole	S. 80° E.	34.18'
Center line Brass Cap in Concrete	(U.S.G.S. Monument)	S. 26° W.	82.48'
Northeast Corner	Railroad Rail Fence Post	N. 84° W.	31.35'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 9-8-98