

**SURVEY & REMONUMENTATION**

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

1  
2  
APR 27 1995

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1976<sup>94</sup> DEC 14 PM 2 39

For corners in

<u>Kalamazoo</u> <small>(County)</small>	Located In:	Corner Code #
Schoolcraft Township	T <u>4</u> S R <u>11</u> W	<u>G-10</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*James J. [Signature]*  
CLERK-REGISTER

LIBER 1 PG 1208

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on June 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1826: U.S. Government Survey; Set 1/4 Section Post.  
Br. Oak 8" North 09° East 79 Lks  
Br. Oak 8" South 67½° West 81 Lks  
Br. Oak 10" in the Line

1879: F. Hodgman, County Surveyor; Bisected East line Section 28 and set stake and stone.  
Elm 6" South 63° East 84½ Lks

1889: F. Hodgman, County Surveyor; See above. Set Post.  
Pine North 49° East 88½ Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994; Found tile in monument box. 1943 Witnesses from file of Wilkins & Wheaton Engineering found.

In Line with Fence South  
16" Pine North 48° East 57.70' (F. Hodgman Witness of 1889. Recently cut down)  
Southwest Corner House Northeast 125.12'

**RATIFIED**  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
9-15-94 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 East 1/4 Post Section 28, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994. Found 3" round tile as called for in 1889 remonumentation survey by F. Hodgman and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed a remonumentation sleeve over tile and a new monument box over.

Northeast Corner (Top)	Railroad Rail Fence Corner	South 08° West	30.73'
PK Nail in Southeast Side	Power Pole	North 50° West	53.49'
PK Nail in Southwest Side	15" Maple	South 48° West	31.89'
PK Nail in North Side	18" Cherry	South 50° East	67.13'
CL "XY" Avenue		North	1.70'
CL 18th Street		East	11.2'

Signed by *Robert E. Snell*

Date 12-14-94

Surveyor's Michigan License No. 9734