

MAY 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Kalamazoo
(County)
Schoolcraft Twp.

Located In:

Corner Code #

- | | | |
|--------------------------------------|-------------------------------|-------------|
| 1. Public Land Survey | T <u>4</u> S. R. <u>11</u> W. | <u>G-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

LIBER 1 1461
 1996 MAR 25 PM 3 30
 STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
James Hodgman
 COUNTY REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on February 7, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors; Set post corner to Sections 33 & 34.
 Tamarac 5" N. 69° E. 15 lks.
 Tamarac 7" N. 21° W. 6 lks.
- 1875: F. Hodgman, County Surveyor; found stake from 2 dead witnesses. Set stake and iron.
 Tamarac 6" N. 21° W. 10 lks.
 Tamarac 10" East 20 lks.
- 1889: F. Hodgman, County Surveyor; found stake and bearing trees as above, set post.
 Maple 6" S. 29° E. 23 lks. Birch 6" S. 31° W. 47 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1996: Found tile in low land marsh sticking 3"+ above surface. Tile is 603'+ East of P.C. in mint road and 53' South of toe of slope (edge of marsh).
 3" Galvanized fence post S. 60° E. 35.2'
 1" Iron pipe S. 60° E.+ 35.6' (Used as Northeast corner of Section 4, T. 5 S., R. 11 W. #169-60 Milburn Peat).

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 3-21-96 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13: Southeast corner, Section 33, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on March 21, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top as placed in 1888 Remonumentation survey by F. Hodgman, County Surveyor, tile is 3"+ above surface. Placed Remonumentation sleeve over tile.
- | | | | |
|-----------------------|-----------|-----------|--------|
| PK Nail in West side | 12" Maple | N. 05° W. | 5.27' |
| PK Nail in North side | 10" Maple | N. 76° E. | 14.44' |
| PK Nail in East side | 10" Maple | S. 10° W. | 8.67' |
| PK Nail in North side | 12" Maple | S. 70° W. | 21.84' |

Signed by *Robert E. Snell*

Date 3-25-96

Surveyor's Michigan License No. 9734