

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SCHOOLCRAFT TWP.

KALAMAZOO Located in: Corner Code #
(County)

1. Public Land Survey T 4 S R 11 W H-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD

'94 DEC 15 PM 1 37

James [Signature]
 CLERK-REGISTER

LIBER 1 PG 1231

Register of Deeds Stamp & File Number

I, Allen H. McMachen a field survey on October 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1880'S - F. Hodgeman C.S. Place Clay Tile Post during official Township Remonumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found broken top section of Clay Tile leaning, Dug down and found bottom section of Tile undisturbed.

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 11-17-94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Found Clay Tile is accepted as a careful & faithful perpetuation of the original corner. Removed broken top section of Clay Tile and placed Harrison Monument over bottom section of Tile.
 Accessories:

- Nail & Tab in 12" Oak N. 30° E. 32.79'
- Nail & Tab in 12" Oak WEST 21.84'
- Nail & Tab in 36" Oak S. 20° W. 25.32'
- Nail & Tab in 18" Oak N. 35° W. 29.14'

Signed by Allen H. McMachen Date 11/30/94
 Surveyor's Michigan License No. 16935

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												