

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> (County)	Located in:	Corner Code #
Schoolcraft Township		
1. Public Land Survey	T 4 S R 11 W	I-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
93 NOV 4 PM 3 43  
1 PG 1008  
LIBER  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John G. Kester, in a field survey on July 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Post in Mound in Prairie no accessories. Survey by Ed Strong, 1881, Found Stone, Accessories: Cherry 4 S48-10W 84½, Maple 7 S68W 113½. Remonumentation by F. Hodgeman, 1889, Found Stone & Brick of former survey and Bearing Trees all in place. Set Post (Solid Clay Tile with "X" on top) with Stone alongside.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Original Corner Post not recovered.  
Remonumentation Corner set by F. Hodgeman not recovered. It appears that road construction may have removed all traces of the above corner evidence.  
Found Monument Box over Concrete Cylinder encasing ½" Iron Rod 3½' long.

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
I-7, Section Corner 14, 15, 22 & 23, T4S-R11W, Ratified by Kalamazoo County Remonumentation Program Peer Group on August 19, 1993. Found Concrete Cylinder encasing ½" Iron Rod 3½' long and is accepted as the best available evidence of the position of the original corner. Removed Monument Box and Concrete encased Iron Rod. Placed 30" Harrison Monument in its place and placed Monument Box over Corner.

- Set P.K. in P.P. N45E 73.55'
- Set P.K. in P.P. N30W 74.62'
- Set P.K. in P.P. N60W 80.80'
- Set P.K. in P.P. S45W 42.87'
- 28" Maple S71W 75.89'

Signed by [Signature] Date 11-4-93

Surveyor's Michigan License No. 16046  
Kalamazoo County Road Commission

