

SURVEY & REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

1 APR 27 1995

2 COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 DEC 14 PM 2 39

For corners in

<u>Kalamazoo</u> <small>(County)</small>	Located In:	Corner Code #
Schoolcraft Township	T <u>4 S</u> R <u>11 W</u>	<u>I-11</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James J. [Signature]
CLERK-REGISTER

LIBER 1 PG 1209

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on May 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1826: U.S. Government Survey; Set Post. Corner to Sections 26, 27, 34 and 35.
R. Oak 12" South 70° East 22 Lks
W. Oak 13" North 30° East 14½ Lks
1889: F. Hodgman, County Surveyor; Found marked stone and bearing tree of resurvey. Set Post.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994: Found 1" x 12" iron pipe, 3" below pavement with a 2' long segment of tile below.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7-21-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-11 Southeast Corner Section 27, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found 3" clay tile 2' in length, as called for in 1889 remonumentation survey done by F.Hodgman and is accepted as a careful and faithful perpetuation of the position of the original corner. Lowered tile and placed a 20" Harrison monument and monument box over.

PK Nail in East Side	15" Oak	North 08° West	53.34'
PK Nail in Northeast Side	Double 14" Oak	North 50° West	63.65'
Exist. Nail/Tab in North Side	Power Pole	South 66° West	54.75'
PK Nail in East Side	16" Walnut	South 06° West	42.28'
CL of "Y" Avenue		North	0.75'

Signed by *Robert E. Snell* Date 12-14-94

Surveyor's Michigan License No. 9734