

**SURVEY &  
REMONUMENTATION**

OCT 06 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Schoolcraft Township

<u>KALAMAZOO</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 4S R 11W	I-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

LIBER 2 PAGE 166  
97 JUL 29 AM 11 01  
STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
Clerk - Register  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on May 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1825: United States Government Surveyors; Set Post corner to Sections 34 and 35.  
Beech 18" North 47° East 47 Lks  
Beech 18" North 81° West 49 Lks
- 1889: F. Hodgman, County Surveyor; "Found stake standing 60 Lks West of stake, corner to Sections 2 and 3 of which bearing trees are standing and stake correct. Set Post."  
Beech 4" North 07° East 51 Lks  
Beech 10" North 74° East 35 1/2 Lks

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1997: Found 3" round tile with "x" on top at surface of ground in a beech forest. (Top section cracked) and a second tile below on high ground West of Kettle (sinkhole). A stone (26" x 18" x 8") lies Southwest, 1.80' and a 2 1/2" iron pipe (St. Joe County Corner Sections 2 and 3, T. 5 S., R. 11 W.) lies East, 39.90'.  
Note: F. Hodgman calls for 60 Lks jog (39.60').

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**  
6-19-1997

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-13 Southeast Corner Section 34, T. 4 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on June 19, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found [and adjusted(see B. Above)] 3" round tile with "x" on top as placed in 1889 remonumentation survey by F. Hodgman, County Surveyor. Placed remonumentation sleeve over tile.

PK Nail in North Side	18" Beech	North	74°	East	10.52'
PK Nail in North Side	15" Beech	South	46°	West	9.61'
PK Nail in North Side	16" Beech	South	89°	West	31.84'
PK Nail in East Side	18" Oak	North	38°	West	17.39'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 7-28-97