

SURVEY &
REMONUMENTATION

AUG 22 1995

COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 MAR 23 PM 4 09

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SCHOOLCRAFT TWP.

KALAMAZOO
(County)

Located In:

Corner Code #

James [Signature]

CLERK-REGISTER

LIBER

1 PG 1285

Register of Deeds Stamp & File Number

- | | | |
|--------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T <u>4</u> S R <u>11</u> W | <u>J-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | ● | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Allen H. McMachen field survey on February 2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - R. Clark, D.S., Set Quarter Section Post
W. Oak 13" S. 44° E. 33 lks.
W. Oak 14" N. 21° E. 34 lks.

1872 - S. Hodgeman, D.L.S., Found stake hole, correct by roots of both witness. Set pointed Stone and side Stone NORTH 50 lks.

1889 - F. Hodgeman, C.S., Found Stone set for corner set Post with side Stone 50 lks. NORTH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "PK" Nail at intersection of previous witnesses. Dug and found monument box 6" below surface with I.W.M. Iron inside. Removed Iron and box and found Flat Stone with no markings 1.8' below surface. Removed Stone and found Clay Tile 2.2' below surface. "PK" Nail, Iron and found Tile were in alignment.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
R. [Signature]
3/16/95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison monument over existing Tile and monument box over. Accessories:

- "PK" Nail (existing) in W. Face U. Pole N. 30° E. 70.27'
- Top of N.E. corner 2"x2" concrete post S. 10° E. 29.30'
- "PK" Nail in N.E. Face U. Pole S. 04° E. 46.16'
- Nail & Tab W. Face 18" Spruce S. 45° W. 36.14'

Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 3/22/95