

SURVEY &
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Schoolcraft Township		
1. Public Land Survey	T <u>4</u> S R <u>11</u> W	<u>J-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
93 NOV 4 PM 3 43
CLERK-REGISTER
Jessica [Signature]
LIBER 1 PG 1009
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John G. Kester, in a field survey on August 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Set Post, Accessories: W Oak 14 N44W 83, W Oak 16 S45W 88. Survey by Ed Strong, 1881, Found Stone - 2 U S Stumps, Accessories: Pepperidge 6 S42W 58. Remonumentation by F. Hodgeman, 1889, Found Stake of old survey midway between Section Corners. Set Post (Solid Clay Tile with "X" on top), Accessories: Maple 10 N25W 63 Lks, Pepperage 6 S-W 58 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Original Corner Post not recovered.
Found 1/2" Iron in Monument Box over Solid Clay Tile with "X" on top called for in 1889 Remonumentation by F. Hodgeman, Accessories gone.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-7, S1/4 Corner Section 14, T4S-R11W, Ratified by Kalamazoo County Remonumentation Program Peer Group on August 19, 1993. Found Solid Clay Tile with "X" on top called for in 1889 Remonumentation and is accepted as a careful and faithful perpetuation of the position of the original corner. Removed Monument Box and 1/2" Iron. Placed 30" Harrison Monument above Tile and placed Monument Box over Corner.

- Set 1/2" Rebar South 32.58'
- Set P.K. Nail in 7" Elm S70E 82.76'
- Set P.K. Nail in 5" Elm N40E 48.08'
- Set P.K. Nail in 6" Elm N50W 49.07'

Signed by *John A. Kester* Date 11-4-93

Surveyor's Michigan License No. 16046
Kalamazoo County Road Commission