

SURVEY & REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE,
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 14 PM 2 39

For corners in **COMMISSION**

Kalamazoo (County)
Schoolcraft Township

1. Public Land Survey	Located In:	Corner Code #
	T 4 S R 11 W	J-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James J. Jones
CLERK-REGISTER

LIBER 1 PG 1210

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on May 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826: U.S. Government Survey; Set 1/4 Section Post.

Y. Oak 11" South 39 1/2° East 38 Lks
Y. Oak 14" South 82° West 23 Lks

1889: F. Hodgman, County Surveyor; Found stone said by Theron Adams to have been kept in place for more than twenty years for the Corner. No bearing trees left and no other evidence of Corner. Set Post.

Hickory 12" South 83 1/2° West 172 Lks
Hickory 12" South 09° East 190 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 1/2" x 24" iron rod at surface. Found tile 3' below surface, next to a notched stone.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 South 1/4 Post Section 26, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found tile as called for in 1889 remonumentation survey by F.Hodgman and is accepted as a careful and faithful perpetuation of the position of the original corner. Left tile and stone in place and placed a 20" Harrison monument and monument box at the surface.

CL "Y" Avenue In Line
PK Nail in South Side 36" Maple North 55° East 39.60'
PK Nail in West Side Power Pole South 30° East 87.45'
PK Nail in South Side Telephone Pole South 72° West 82.31'
PK Nail in North Side Telephone Pole North 32° West 42.72'
CL 21st Street East 1.5'

Signed by Robert E. Snell Date 12-14-94

Surveyor's Michigan License No. 9734