

SURVEY & REMONUMENTATION

MAY 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'96 APR 22 PM 4 23

For corners in
Kalamazoo
(County)
Schoolcraft Twp.

Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>4</u> S. R <u>11</u> W.	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James Young
CLERK-REGISTER

LIBER 1 PAGE 1483

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on February 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; set 1/4 Section post.

W. Oak 7" N. 21 $\frac{1}{2}$ ⁰ E. 60 lks.
W. Oak 5" N. 28⁰ W. 123 lks.

1889: F. Hodgman, County Surveyor; found stake with brick around at intersection of roads North and East. Set post.

Maple 12" N. 36⁰ E. 85 lks.
Hickory 4" S. 33⁰ W. 19 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1981: Al McMachen, R.L.S. #16935; L.C.R.C. L-1, P-849. Tile.

18" Maple N. 45⁰ E. 56.00'
14" Walnut West 45.00'
30" Hickory S. 20⁰ W. 12.30'

1996: Found 3" round tile with "x" on top in intersection of roads North and East.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

3/21/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13: South 1/4 post, Section 35, T. 4 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on March 21, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top below surface of the ground as set by F. Hodgman in 1889 Remonumentation Survey. Placed remonumentation sleeve over tile.

West Edge	Pavement	East	11.5'
PK Nail in East Side	34" Hickory	S. 14 ⁰ W.	12.27'
PK Nail in North Side	18" W. Cherry	N. 80 ⁰ W.	35.25'
PK Nail in South Side	8" Maple	N. 40 ⁰ W.	14.06'
PK Nail in East Side	12" Elm	N. 16 ⁰ W.	22.85'

Signed by Robert E. Snell

Date 4-19-96

Surveyor's Michigan License No. 9734