

FEB 18 1994

LIBER

1 PG 1011

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Kalamazoo (County), Schoolcraft Township, and numbered items 1-5 for Public Land Survey, Property Controlling, Miscellaneous, and Lot No/Private Claims.

CLERK - REGISTER

Handwritten signature of the Clerk-Register.

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
93 NOV 4 PM 3 44

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13, containing numbers 1-36 and a black dot in cell G7.

I, John G. Kester, in a field survey on August 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Set Post, Accessories: Y Oak 20 N6W 30, W Oak 11 S74W 11 1/2. Survey by F. Hodgeman, 1875, Found Stake, Stone & Brick for Corner in line with fences North & South, Accessories: Y Oak 24" S60E 82 1/4 Lks, S.E. corner of base of Smith Monument N12W 66 3/4 Lks. Remonumentation by F. Hodgeman, 1889, Found Stake, Stone & Brick of previous survey. Set Post (Solid Clay Tile with "X" on top), Accessories: Same as previous survey in 1875.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Original Corner Post and Accessories not recovered. Found 1" Pipe in Monument Box above Solid Clay Tile with "X" on top with stone around as called for in 1889 Remonumentation by F. Hodgeman, Accessories: S.E. Corner Smith Monument 43.95', N12W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: L-7, S 1/4 Corner Section 13, T4S-R11W, Ratified by Kalamazoo County Remonumentation Program Peer Group on August 19, 1993. Found Solid Clay Tile with "X" on top called for in 1889 Remonumentation and is accepted as a careful and faithful perpetuation of the position of the original corner. Removed Monument Box and 1" Pipe. Placed 20" Harrison Monument above Tile and placed Monument Box over Corner.

- S.E. Corner Smith Monument N12W 43.95'
N.W. Corner House South 41.13'
Set P.K. Nail in P.P. S65E 66.37'
Set P.K. Nail in P.P. N55E 47.03'

Signed by [Signature] Date 11-4-98
Surveyor's Michigan License No. 16046
Kalamazoo County Road Commission

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP

