



LC-000026
 Page: 1 of 1
 09/17/1999 03:11P
 Bk-2 Pg-479

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

corners in Schoolcraft Twp.

Kalamazoo _____ Located in: _____ Corner Code # _____
 (County)

1. Public Land Survey T 4 S R 11 W L-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SURVEY & REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert E. Snell, in a field survey on June 23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors, J. Mullet; set 1/4 Section post.
 Y. Oak 14" N. 58 1/2° E. 329 lks. W. Oak 18" N. 35 3/4° W. 350 lks.
- 1889: F. Hodgman, County Surveyor; "Ran east, true line from South 1/4 post of Section 35, 60.62 chains and set post 9 lks. (5.94') West of stone for 1/4 corner of Section 1, Park. Wh. Oak 16" N. 63 1/2° E. 127 1/2 lks., R. Oak 12" S. 53 1/4° E. 46 lks."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1916: G. Eagleton, County Surveyor (St. Joseph); 4" tile West 0.09 chains (Kalamazoo County Corner) of stake for North 1/4 Section 1, Park Township.
- 1999: Found 1/2" x 14" iron with cap above 3" round tile, top broken off. Noted: 1/2" iron in monument box, East 6.52', Nail/Tab in Southeast face Oak N. 60° W. 45.42'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13: South 1/4 post, Section 36, T. 4 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on August 19, 1999 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile, set by F. Hodgman in 1889 Remonumentation survey. Placed 15" of 20" Harrison monument in concrete in monument box.

PK Nail in South Side	42" Oak	N. 56° E.	54.33'
PK Nail in West Side	12" W. Cherry	S. 14° E.	29.60'
PK Nail in South Side	14" Oak	N. 40° W.	43.56'
PK Nail in South Side	7" Hickory	N. 16° W.	32.00'

Signed by Robert E. Snell
 Surveyor's Michigan License No. 9734

Date 9-18-99

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 8-19-1999