

**SURVEY & REMONUMENTATION**

JUL 23 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Schoolcraft Township Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Kalamazoo (County)

1. Public Land Survey	T <u>4S.</u> R <u>11W.</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 2 PAGE 139  
 97 MAR 16 PM 3 50  
 STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 J. J. Johnson  
 CLERK - REGISTER  
**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 6. IWM Job No. 18862

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on December 18, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 10/31/1825 - John Mullett, D.S., "Set temporary six mile post" (80 chains North of S.E. corner, Sec. 1, Schoolcraft Twp.)
- 11/17/1825 - John Mullett, D.S., (running South Boundary of Pavilion Twp.) "Intersected range line 339 links South of temporary six mile post. Set post at intersection corner to Townships 3 and 4 South, Ranges 10 and 11 West" W. Oak 14" N. 87° E. 86 lks., Y. Oak 7" S. 37½° W. 114 lks.
- 1888 - F. Hodgman, C.S., "Found stake standing S. 87° W. 86 lks. from W. Oak bearing standing, set post. Maple 10" South 10½ lks."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found clay tile at surface of ground between tree roots, matching 1888 witness to Maple.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 12-30-1993

(This corner is common with A-13, Pavilion Twp., M-13, City of Portage and A-1, Brady Twp.)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found clay tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed standard sleeve over existing tile, Accessories:

- Nail & Tab in East face 14" Oak N. 05° E. 27.75'
- Nail & Tab in West face Triple Maple S. 40° E. 29.92'
- Nail & Tab in North face 8" Hickory S. 82° E. 35.50'
- Nail & Tab in East face 42" Maple South 6.73'



*R.E.S.*

Signed by Allen H. McMachen Date 1/30/97  
 Surveyor's Michigan License No. 16935