

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 088

For corners in Schoolcraft Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T4S R11W	M-02
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
96 NOV 15 PM 1 59
Kalamazoo County
CLERK-REGISTER
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Sept. 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
10/17/96

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; set 1/4 post.

W. Oak 10" S. 21 1/2° W. 58 lks.
W. Oak 8" N. 64° W. 78 lks.

1889: F. Hodgman, County Surveyor; found stake in center of road and in line with fences North and South. Set post.

Cherry 5" N. 02° E. 59 1/2 lks.
Oak 6" S. 01° E. 80 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1973: Allen McMachen, R.L.S. #16935; L.C.R.C. L-1, P-233, found tile 1' deep.
Utility Pole N. 45° E. 60.70' Utility Pole N. 05° W. 27.80'
36" Cherry North 39.85' 3" Hickory South 14.60'

1976: Don Gilchrist, R.L.S. #13583; L.C.R.C. L-1, P-689 - tile.
30" Cherry N. 02° E. 39.84' P.P. N. 45° E. 60.70'
6" Oak S. 05° W. 42.56' Mon. North 33.00'

1996: Found tile in monument box, 3.5' South of traveled center line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-02: East 1/4 post Section 1, T. 4 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on October 17, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile as set by F. Hodgman in 1889 Remonumentation Survey, in monument box. Placed remonumentation sleeve over tile in monument box.

1/2" Iron in Concrete Plat Monument	North	33.00'
PK Nail in West Side	South	14.85'
PK Nail in West Side	N. 45° W.	38.25'
PK Nail in South Side	N. 45° E.	61.45'
	14" Hickory	
	Db1. 10" Hickory	
	Power Pole	

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 11-14-96